



CABLE : MUST use 2Hr Fire Rated Screened cable - Stranded - Outer Insulation must be RED

SIGNS : Max Number of Signs or LCS is 7 units on 485 Comms
 Status Power can support 3 signs only - for additional signs need separate power supply as shown

FIREPRO : Max of 4 FirePro Generators to each bank in Sequential Activator.
 Use of Splitter Leads will reduce field Cabling.
 Connection to FirePro Units to use 3 Pin Deutch Plugs to allow for connection of Test Modules and Servicing.