

Central Exchange – UPS Room

- Volume – 69.92 cu mtrs.
- Certification - UL2775/AS4487 certification design calculation.
- Design concentration 7,635 grams
- Total concentration recommended – 8,000 grams -104%
- Generators - 2 x 3000g & 1 x2000g

