

### **Earth Station Equipment Room-**

- Volume – 231 cu mtrs.
- Certification - UL2775/AS4487 certification design calculation.
- Design concentration 25,225 grams
- Total concentration recommended – 22,800 grams -102%
- Generators - 4 x 5700g generators & 1 x 3000g
- Stream length 8mtrs for 5700g generator 28kg each & 4Mtrs for 3000g.