

### **Earth Station UPS Room-**

- Volume – 157.5 cu mtrs.
- Certification - UL2775/AS4487 certification design calculation.
- Design concentration 17,199 grams
- Total concentration recommended – 20,100 grams -116%
- Generators - 3 x 5700g generators & 1 x 3000g
- Stream length 8mtrs for 5700g generator 28kg each & 4Mtrs for 3000g.